


This article was downloaded by: [Jiang, Bin]

On: 16 March 2010

Access details: Access Details: [subscription number 919901400]

Publisher Taylor & Francis

Informa Ltd Registered in England and Wales Registered Number: 1072954 Registered office: Mortimer House, 37-41 Mortimer Street, London W1T 3JH, UK



## International Journal of Geographical Information Science

Publication details, including instructions for authors and subscription information:

<http://www.informaworld.com/smpp/title~content=t713599799>

### Automatic generation of the axial lines of urban environments to capture what we perceive

Bin Jiang <sup>a</sup>; Xintao Liu <sup>a</sup>

<sup>a</sup> Department of Technology and Built Environment, Division of Geomatics, University of Gävle, Gävle, Sweden

Online publication date: 16 March 2010

**To cite this Article** Jiang, Bin and Liu, Xintao(2010) 'Automatic generation of the axial lines of urban environments to capture what we perceive', International Journal of Geographical Information Science, 24: 4, 545 — 558

**To link to this Article:** DOI: 10.1080/13658810902950351

**URL:** <http://dx.doi.org/10.1080/13658810902950351>

PLEASE SCROLL DOWN FOR ARTICLE

Full terms and conditions of use: <http://www.informaworld.com/terms-and-conditions-of-access.pdf>

This article may be used for research, teaching and private study purposes. Any substantial or systematic reproduction, re-distribution, re-selling, loan or sub-licensing, systematic supply or distribution in any form to anyone is expressly forbidden.

The publisher does not give any warranty express or implied or make any representation that the contents will be complete or accurate or up to date. The accuracy of any instructions, formulae and drug doses should be independently verified with primary sources. The publisher shall not be liable for any loss, actions, claims, proceedings, demand or costs or damages whatsoever or howsoever caused arising directly or indirectly in connection with or arising out of the use of this material.

## Automatic generation of the axial lines of urban environments to capture what we perceive

Bin Jiang\* and Xintao Liu

*Department of Technology and Built Environment, Division of Geomatics, University of Gävle, Gävle, Sweden*

*(Received 27 November 2008; final version received 22 March 2009)*

Based on the concepts of isovists and medial axes, we developed a set of algorithms that can automatically generate axial lines for representing individual linearly stretched parts of open space of an urban environment. Open space is the space between buildings where people can freely move around. The generation of the axial lines has been a key aspect of space syntax research, conventionally relying on hand-drawn axial lines of an urban environment, often called axial map, for urban morphological analysis. Although various attempts have been made towards an automatic solution, few of them can produce the axial map that consists of the least number of longest visibility lines, and none of them really works for different urban environments. Our algorithms provide a better solution than existing ones. Throughout this article, we have also argued and demonstrated that the axial lines constitute a true skeleton, superior to medial axes, in capturing what we perceive about the urban environment.

**Keywords:** visibility; space syntax; topological analysis; medial axes; axial lines; isovists

### 1. Introduction

Open space of an urban environment or of a city is the space where people can freely move around, and it is in contrast to closed spaces such as buildings and street blocks. Open space can be thought of as something between closed spaces and can be represented as a complex polygon with holes. The holes denote closed spaces, i.e. the buildings and street blocks. Open space of a city forms one continuous piece rather than separate parts, because people can travel from anywhere to anywhere else in a city. For the purpose of modelling human movement, open space has been of primary interest, being the modelling target in space syntax (Hillier and Hanson 1984). It is done through representing open space as many perceivable units, and further forming a connectivity graph consisting of nodes representing individual units and links if the units are intersected. The connectivity graph can be used to analyze and rank the status of the individual units for understanding the underlying topology of the city. The representation of open space can be in different ways.

One classic representation is to represent open space as many interconnected axial lines, each depicting a linearly stretched part of open space. The axial lines constitute what is often called an axial map that can be thought of as a skeleton of the city. The axial map is supposed to consist of the least number of longest axial lines. Its generation is achieved by manually

---

\*Corresponding author. Email: bin.jiang@hig.se

drawing the first longest visibility line, followed by the second longest, the third longest and so on, until the entire open space is covered with interconnected axial lines. The drawing procedure can be justified by the partitioning (or discretization) of a large-scale space (i.e. the continuous open space) into numerous discrete small-scale spaces, each of which is represented by an axial line – the longest visibility line for the small-scale space. A major difference between a large-scale space and a small-scale space lies in whether it is perceivable from a single vantage point: no for a large-scale space and yes for a small-scale space. The notions of large-scale and small-scale spaces constitute the foundation of our proposed algorithms for automating the axial lines or the axial map.

Space syntax has been widely applied to various urban related studies such as traffic modelling for pedestrians and vehicles, crime analysis, and human wayfindings in complex urban environments (Hillier 1996). Such studies significantly rely on the axial maps, which are currently created by hand. The hand-drawn map has been a very controversial aspect of space syntax (e.g. Jiang and Claramunt 2002, Ratti 2004). Because of this, many alternative spatial representations have been suggested, for instance, visibility graph (Turner *et al.* 2001), point-based space syntax (Jiang and Claramunt 2002) and more alternative representations based on street networks (e.g. Thomson 2003, Jiang and Claramunt 2004, Jiang *et al.* 2008). In the meantime, efforts have been made towards automatic generation of the axial map in the space syntax community (c.f., next section for an overview). However, despite these efforts, few solutions can produce the axial map that consists of the least number of longest visibility lines (or axial lines), and none of them really works for different urban environments. In this article, we provide a solution that can automatically generate the axial map that consists of the least number of longest axial lines, thus making space syntax analysis more objective and more meaningful for urban morphological studies. The contributions of this article are two-fold, which are reflected in the article title. First, it provides a simple yet elegant solution to the automation of the axial lines through the novel concept of bucket. Second, it discovers an important statistical difference between the medial axes and the axial lines of urban environments, i.e. the axial lines can capture much better than medial axes what we perceive about urban environments.

This article is structured as follows: The next section presents an overview about axial lines related concepts and various efforts towards automation of the axial map. Section 3 describes in detail the major motivation, ideas and pseudocodes of our algorithms, which are implemented as a research prototype. Section 4 reports our primary experiments of different urban environments and assesses a major statistical difference between medial axes and axial lines. Finally Section 5 concludes and points to further work in the future.

## 2. Axial lines related concepts and efforts towards an automatic solution

Both axial lines and medial axes (Blum 1967; Blum and Nagel 1978) are considered to constitute a skeleton of urban environments, but they differ fundamentally. Take a rectangle-shaped space for example (Figure 1a), in which medial axes are indicated by the dashed lines. The medial axes or skeleton can be thought of as the loci of centers of bi-tangent circles that fit entirely within a shape. The skeleton can also be produced by the thinning operation in image processing. The medial axes have a nature of sensitivity, i.e. a slight change in the shape can cause a dramatic change to its skeleton (Figure 1b and c). Because of this sensitivity, the skeleton based on the medial axes has difficulty in forming a natural decomposition of a shape into a set of basic units that mirror the shape we perceive (Katz and Pizer 2003). For example, despite two tiny convex and concave parts,




Figure 1. Illustration of Blum's medial axes and their sensitivity.

both shapes shown in Figure 1b and c are perceived as a rectangle. However, the perceived shape rectangle can hardly be seen from their medial axes. Medial axes can only be effective in capturing the parts we perceived for purely symmetric objects or shapes, and they become defective if they are slightly asymmetric. This can also be seen from the medial axes of the Gassin open space (c.f. Figure 4 later in this article), where each hole is surrounded by a set of precisely defined medial axes. In contrast, the 'roughly' defined axial lines can capture well the parts we perceive – a few longest lines intersected with many shorter ones. It is in this sense that the axial map is a true skeleton of a city, reflecting what we perceive. This point will become clearer when we further illustrate a major statistical difference between medial axes and axial lines in the following experiments.

The initial definition of axial map, given by Hillier and Hanson (1984), is based on a prior definition of the convex map of open space – a complex polygon with holes; Refer to Figure 2 for an illustration of various concepts used in this article. The convex map is 'the least set of fattest spaces that covers the system' (p. 92). The system here is what we refer to as open space. The procedure of generating the convex map seems based on some arbitrary




Figure 2. Illustration of various concepts based on the town of Gassin, (a) open space – the shaded part, closed spaces – the white parts, and outmost boundary – the black line, (b) original convex map, (c) original axial map and (d) all-line map produced from Depthmap.

rule, i.e. ‘simply find the largest convex space and draw it in, then the next largest, and so on until all the space is accounted for’ (p. 98). As a reminder, the space here is what we refer to as open space. Given the definition of convex map, an axial map is defined as ‘the least set of such straight lines which passes through each convex space and makes all axial links’ (p. 92). This definition is a bit vague, for instance, what does it mean by ‘passes through each convex space’? However, the procedure of generating the axial map is less vague, similar to the one for generating the convex map, i.e. ‘first finding the longest straight line that can be drawn . . . , then the second longest, and so on until all convex spaces are crossed and all axial lines that can be linked to other axial lines without repetition are so linked’ (p. 99). This procedure of generating the axial map seems much clearer than in its definition. However, there is no unique partition of a 2D open space into convex polygons, as argued by many researchers, in particular those working in the famous art gallery problem (O’Rourke 1987). Therefore, there are difficulties to draw the least number of axial lines that cover the convex polygons, according to the existing definition. Another related linear representation of open space is called all-line map. It consists of all the lines generated from the process where every pair of the vertices of the holes are linked and extended without intersecting the holes of open space. Without reference to the convex map, the all-line map can be objectively generated, and it has been used in space syntax analysis (Hillier 1996). Attempts have been made towards an automatic derivation of the axial map from the all-line map with a considerable degree of redundancy of lines.

Peponis *et al.* (1997, 1998) suggested an alternative space partition called s-partition, which can be automatically and uniquely generated. The spaces formed by s-partition are called s-partition spaces. Peponis and his colleagues took the s-partition spaces as a sort of convex spaces and used them as a reference to derive an economic set of lines from the all-line map. Their procedure starts with picking up the first axial line with the most crossing points with the underlying s-partition spaces. It continues to the second axial line, which crosses the second most number of s-partition spaces (not crossed by the first axial line), and so on, until no more s-partition space is left. In essence, it is a greedy strategy, with a local optimum to achieve a global optimum. It sounds like an elegant algorithm, but the procedure does not always lead to the axial map, even with some remedy to the procedure. This is the very reason that Peponis *et al.* avoided the use of axial lines and called them m-lines. Besides, this procedure has a problem of resolution, i.e. open space must be significantly simplified before the method can be applied.

Following up the pioneering work by Peponis *et al.* (1997, 1998), Turner *et al.* (2005) developed a procedure to remove the constraint of resolution and suggested another subset elimination technique for reducing the all-line map into the axial map. In the course of the subset elimination, Turner *et al.*’s algorithm considered two constraints: surveillance and topological rings. The surveillance refers to the fact that an entire open space is under surveillance of all the axial lines. If any part of the open space is not under the surveillance, then new axial lines are needed. Every hole is supposed to be surrounded by a topological ring. In case the topological ring is incomplete, new axial lines are again needed to complete it. Despite the improvement, there are still some pathological cases that cannot be solved by the existing solution, as indicated by Turner and his colleagues. More importantly, the algorithm does not always produce the least number of longest axial lines for any urban environment, implying some redundant lines existed.

The previous efforts led by Peponis and Turner stick too dogmatically to the initial definition based on convex partition, yet reflect Hillier and Hanson’s rules rather than what we perceive. Nevertheless, they provided the best solutions so far in terms of

producing the axial map that consists of the least number of longest axial lines. Other efforts do not lead to or target to the axial map. For instance, inspired by the notion of isovists (Benedikt 1979), which is the part of open space that is directly visible from a location, Batty and his colleagues (Batty and Rana 2004; Carvalho and Batty 2005) believed that the dominant direction of an isovist (so-called isovist ridge) can capture a linearly stretched part of open space, and experimented on alternative representations. Unfortunately, the alternative representations they explored are far from the axial map; they avoided this problem and suggested instead to reformulate space syntax because of the impossibility of automatically generating the axial map. Contrary to these efforts, we will illustrate that an automatic solution to the axial map is not only possible, but also algorithmically sound.

### 3. A solution for automating the axial lines based on the concepts of isovists and medial axes

From the previous section, we can see that skeletonization (either the medial axes or the axial lines) is a process that discretizes a continuous open space into many individual lines. The medial axes are composed of numerous medial points of corresponding edges of holes, including also the outmost boundary. Obviously, the medial axes lines could be curved if the corresponding edges do not parallel each other. When it comes to axial lines, the discretization process is not as simple as that of the medial axes. We propose a two-stage solution to this problem (Figure 3). We first discretize open space into numerous rays that significantly overlap each other (i.e. the rays fully filled in open space), and then reduce the rays into an economic set representing the axial lines. Our innovation lies in a simple yet elegant reduction algorithm based on a novel concept of bucket that we developed.

The numerous overlapped rays fully fill the continuous open space. Putting it differently, all parts of open space are crossed by the rays, and all the rays that can be linked to other rays *with* repetition are so linked. This statement sounds like that in the procedure of generating axial lines, ‘first finding the longest straight line that can be drawn . . . , then the second longest, and so on until *all convex spaces are crossed and all axial lines that can be linked to other axial lines without repetition are so linked*’ (p 99, emphasis by the authors). The only difference lies in the fact that the rays are repeated in the sense that some rays can be replaced by others, whereas the axial lines are without repetition, implying that every axial line is unique. In other words, the rays constitute a super set of the axial lines. Through elimination of repeated ones we can obtain an economic set of the axial lines – the least number of longest visibility lines of open space. Now let us describe in detail how the two stages can be achieved.




Figure 3. A two-stage solution to generating axial lines.

It is a pretty straightforward process to generate a full set of rays that entirely cover open space. For each vertex of the medial axes, there is a ray, i.e. the dominant direction of the vertex's corresponding isovist, or simply called an isovist ridge (Carvalho and Batty 2005). The process of generating rays must be exhausted for all the vertices of the medial axes. We also tried to generate a full set of rays by linking every pair of the vertices of the medial axes, but eventually we abandoned this idea because of the intensiveness of the computation. The generated rays are significantly redundant or repeated. To eliminate the repeated rays, we introduce a new concept of bucket. Bucket is defined as a space that is approximated by an axial line, and it is represented as a polygon that surrounds an axial line or a ray (Algorithm I). To remind, every vertex of a medial axis has two associated points (in its corresponding shape edges) from which the vertex is created. This can be clearly seen from Figure 1, where the central points of the circles are the medial axes vertices created from two associated points in the rectangle edges that are tangent to the circles. For a complex polygon with holes, all medial axes vertices are created from the edges of holes or the outmost boundary. Thus every medial axes vertex has two associated points in the edges of holes or in the outmost boundary. This can be equally said that every point in the edges of holes or the outmost boundary has one associated medial axes vertex.

It is through such an association that we derive a bucket for each ray. For example, the ray shown in red in Figure 4c cuts across three Voronoi regions (which are formed by medial axes) of three closed spaces A, B and C. More specifically, the ray with two ending points  $e1$  and  $e2$  cuts the Voronoi regions at vertices  $x1$  and  $x2$ . According to the association mentioned above, we can find four associated points for the ending points, i.e.  $e11$  and  $e12$  for  $e1$ ,  $e21$  and  $e22$  for  $e2$ . In addition, the ray segment  $x1x2$  corresponds to two medial axes segments  $x1y1$  and  $x2y1$  that intersect at point  $y1$ . The point  $y1$  has two associated




Figure 4. Illustration of the solution from (a) medial axes, (b) all the rays generated individual vertices of the medial axes, (c) bucket of a ray and (d) generated axial map (Note: for panel c: thick line = ray, dashed lines = medial axes, gray lines = edges of closed spaces, arrows = association, the boundary of shaded area = bucket generated for the ray).

points  $y_{11}$  and  $y_{12}$ . The two ending points and the associated points can be chained together to form the bucket of the ray. More generally, the points to be chained together are  $e_1, e_2, e_{11}, e_{12}, e_{21}, e_{22}, y_{11}, y_{12}, \dots, y_{n1}, y_{n2}$ , where  $n$  is the intersection points of the corresponding medial axes segments. According to our observation, there are three intersection points in maximum for the medial axes segments. The number of the intersection points could be 0, implying that there is just one medial axes segment corresponding to the ray segment.

The bucket will help us to remove those redundant or repeated rays. The process can be described as follows: The first axial line is obtained by sorting all the rays and selecting the longest. All other rays within the bucket of the axial line will be removed from the ray set, for they are not long enough, violating what we said about the longest visibility lines. This process goes on for the remaining ray set for the second and third longest axial lines and so on, until there is no ray left in the ray set. In the end, we generate a set of axial lines, containing all the longest lines. This is a loop procedure using a global search strategy. The procedure can also be conducted in a recursive fashion and using a local search strategy. The procedure starts with the first longest axial line from the ray set. The second axial line is picked up from those rays directly connected to the first axial line, rather than from all the remaining rays, making it a local search strategy. The second axial line is not necessary to be the second longest at the global scale. This is the major difference between local search and global search: see more details in Algorithm II. Up to this point we have generated an economic set of the axial lines that are connected and cover all parts of open space. It is important to note that the reduction procedure does not change the nature of all the rays, except the removal of redundant or repeated rays.

With Algorithm II, we generate all the rays from the medial axes vertices for open space and then reduce them into an economic set representing the axial lines. Algorithmically, we could do this in a recursive fashion from the very beginning. We start with an arbitrarily drawn line in open space and discretize the line into a series of points. From the points, we generate isovist ridges and remove those repeated ones using the bucket reduction algorithm. For those selected lines, we recursively repeat the above process; see details in Algorithm III. After the recursive process for all locally generated rays, we may need another round of reduction to clean a few lines that are still considered to be redundant, to achieve the least number. This algorithm sounds very simple, but there is a resolution issue involved in the process. We adopt a resolution that is determined by one-third of the smallest distance between two closed holes or between any hole and the outmost boundary. The resolution is proved to be sufficient for generating the axial map.

### Algorithm I: Procedure for extracting a bucket of a ray or an axial line

Input: A ray  $r$  and a complex polygon with holes

Output: The bucket of the ray  $r$

#### Function BucketFormation (ray $r$ )

```

Generate Voronoi regions or medial axes of the complex polygon;
Intersect current ray with the Voronoi regions to obtain partitioned ray segments with
  intersection points  $x_1, x_2, \dots, x_m$ ;
For the ending points  $e_1$  and  $e_2$ , find the associated points:  $e_{11}, e_{12}$  for  $e_1$ , and  $e_{21},$ 
 $e_{22}$  for  $e_2$ ;
For every partitioned ray segment, find the associated medial axes segments, their
  intersection points  $y_1, y_2, \dots, y_n$  ( $n \leq 3$ ), and the associated points:  $y_{11}, y_{12}$  for  $y_1,$ 
 $y_{21}, y_{22}$  for  $y_2$ , and  $y_{31}, y_{32}$  for  $y_3$ ;
The two ending points and the associated points are chained together to form a closed
  polygon called bucket of the ray.

```

**Algorithm II: Loop and recursive procedures of generating axial lines globally**

Input: Open space S

Variables: Ray set R

Output: Axial line set A

```

// Generate ray set R for the entire open space from the vertices of medial axes (MA)
Function Globally_Generate_Ray_Set ()
  Generate medial axes for each closed space;
  For each medial axis
    For each vertex of the medial axis
      Generate isovist ray set I at every one degree direction (0 ~ 360°);
      Select the longest ray (l_ray) with the best connectivity as ridge from isovist
      ray set I;
      Add ray to ray set R;

// Loop version of reduction process
Loop Function Global_Search ()
  Select the longest ray from the ray set R as current axial line in the axial line set A;
  While (the ray set R is NOT empty?)
    Construct the bucket of current axial line;
    If (any ray in the bucket?) Then
      Delete this ray from the ray set R;
      Select the longest ray from the remaining ray set R
      as another axial line in axial line set A;

// Recursive version of reduction process
Select the longest ray from the ray set R as current axial line in the axial line set A;
Recursive Function Local_Search (current axial line)
  BucketFormation(current axial line);
  If (any ray in the bucket?) Then
    Delete this ray from the ray set R;
  Select a subset of rays intersecting the current axial line;
  If (the subset is NOT empty?) Then
    Select the longest ray in the subset as an axial line in
    the line set A;
    Local_search (an axial line);

```

**Algorithm III: Recursive procedure of generating axial lines locally**

Input: Open space S

Variables: Ray set R

Output: Axial line set A

```

// Generate ray set R from individual points of a ray
Arbitrarily draw a line within open space S, and extend it as a current ray;
Recursive Function Locally_Generate_Ray_Set (current ray)
  Generate isovist ridges list along the current ray;
  Current ray = the longest ridge
  BucketFormation (current ray);
  For each ray in isovist ridges list
    If (the ray in accumulative bucket) Then
      Delete this ray from ridges list;
  If (the remaining ridges list is NOT empty?) Then
    Add remaining ray in ridges list to ray set R;
    For each ray in remaining ridges list
      Locally_Generate_Ray_Set (ray);

```

The above algorithms can be justified by the fact that each axial line is a small-scale space that is represented by a bucket, and all those rays within the bucket are considered to be redundant and shall therefore be removed. The key of the algorithms lies in the partitioning of a large-scale open space into many small-scale spaces, each of which is represented by a bucket. The bucket is not necessarily convex, so it is not a small-scale space per se. However, the bucket can roughly be considered to be a small-scale space, because it is visible entirely from an axial line point of view. The set of buckets constitutes the least number of spaces that cover all parts of open space. The above algorithms have been put together as a research prototype namely AxialGen (Jiang and Liu 2009), which has been released for academic uses.

#### 4. Experiments with a set of urban environments

We made a series of experiments with a set of test cases to (1) demonstrate how able the axial lines are in capturing units or parts we perceive about urban environments and to (2) assess the validity of the axial lines and computational complexity. Some of the test cases are taken from the space syntax literature, whereas others are some typical street patterns (Jacobs 1995). As we can see from Figure 5, all axial maps generated, including a few pathological cases identified previously in the literature, consist of the least number of the longest visibility lines. The computation of an axial map involves the derivation of the medial axes, the rays that cover the entire open space and the reduction of the rays into an economic set being the axial lines. With the current implementation, the medial axes are created using the operation of distance transformation or distance map, which can be efficiently done with most geographic information systems software. We adopt binary space partitioning that can greatly speed up the process of generating the rays (Sung and Shirley 1994). In terms of computational complexity, the most time-consuming part is attributed to the reduction process, where ray-in-polygon operation consumes too much computational resource. The computation is still deemed very intensive (Table 1), but the axial lines generated are nearly perfect. All the axial lines shown in both Figures 5 and 6 are automatically generated using the local search option of Algorithm II. It should be noted that with the global search option




Figure 5. The first group of experiments of urban environments taken from the space syntax literature: (a) T-shape, (b) Three-block case, (c) Four-block case, (d) Eight-block case, (e) Barnsbury and (f) National Gallery London (rotated by 90°).

Table 1. Time cost for generating the axial lines and the number of the axial lines and that of the medial axes (The computation was done on a desktop computer: RAM: 4 GB, CPU: 2.4 GB, 4 cores, Hard disk: 250 GB, OS: Windows XP)

Patterns	Time cost (seconds)	Medial axes	Axial lines
Barnsbury	320	103	55
Gassin	90	72	39
Mississauga	77	81	23
Barcelona	1611	689	217
Copenhagen	509	381	115
London	967	437	134
New York	2476	262	22
Paris	1594	597	160
Rome	1440	797	254
San Francisco	658	396	67
Toronto	227	175	46




Figure 6. The second group of experiments using the typical street patterns. (a) Mississauga, (b) Barcelona, (c) Copenhagen, (d) London, (e) New York, (f) Paris, (g) Rome, (h) San Francisco and (i) Toronto.

of Algorithm II or Algorithm III, it leads to a similar perfect result, given that the parameters are appropriately set.

We can also note from the experiments that the axial lines, rather than the medial axes, are able to capture the individual parts we perceive about an urban environment towards an




Figure 7. A major statistical difference between the medial axes and the axial lines: (a) Non-hierarchical structure with the medial axes whose length exhibits a Gaussian-like distribution and (b) Hierarchical structure with the axial lines whose length demonstrate a power law-like or heavy tail distribution.

understanding of underlying urban structure, i.e. a very few long axial lines interconnected to many shorter ones. Usually, the number of the axial lines is far less than that of the medial axes (Table 1). Importantly the axial lines demonstrate a hierarchy, which is a key feature of complex systems (Simon 1962) and that of urban systems as well (Salingeros 2005, Jiang 2009). This hierarchical structure is clearly absent in the skeleton representation by the medial axes. Taking the case of Paris as an example, its medial axes all have a similar length,




Figure 8. Axial maps visualized according to local integration for showing underlying hierarchical structure of the street patterns.




Figure 9. A missing axial line (black) with National Gallery London (rotated by  $90^\circ$ ).

exhibiting a Gaussian-like distribution, whereas its axial lines bear a power law-like or heavy tail distribution (Figure 7). The axial map captures the parts we can conceive or what we truly perceive, being the image of the city (Lynch 1960). With the axial map, a few longest lines, which are visually dominating, constitute the landmarks that can be distinguished from all other axial lines. This image of the city can further be seen from the axial maps visualized (Figure 8) according to local integration, one of the key space syntax metrics (e.g. Jiang 2009, 2007), with red representing the most integrated lines, and blue the most segregated ones. The reader can assess visually how the kind of hierarchical structure appears within the different urban environments.

Despite the advantages we have shown, our algorithms are not without its problems. The bucket algorithm works only for linearly stretched parts that are formed by two closed spaces. The reader may have noticed already that there are a few axial lines missing from the experimented cases. The missing lines occurred in places where one closed space has a concave part, forming a linearly stretched space penetrating deep into the closed space. Figure 9 shows such a missing axial line in the case of National Gallery London. This problem happens in particular when two concave parts, from two closed spaces, respectively, form a linearly stretched space penetrating in two opposite directions deep into the two closed spaces. Strictly speaking, the linearly stretched part is indeed between two closed spaces, but it is actually created by each closed space. This is indeed a constraint of the current bucket algorithm. A tentative solution is to detect those concave parts and add possible missing lines. However, this remedy procedure may have some side effects, for instance, slowing down computational process.

## 5. Conclusion

The least set of longest visibility lines or the axial lines that cover entire open space of an urban environment constitute the backbone of the environment and form what we perceive about open space. We have argued and demonstrated throughout this article that the axial

lines are superior to the medial axes in skeleton extraction. We developed a set of algorithms that can automatically generate the axial lines. We abandoned the initial idea of deriving the axial lines based on the convex partitions and adopted instead the idea that an axial line is simply a small-scale space that can be represented by a bucket. The concept of bucket is probably the most novel contribution of this article.

As tested with various urban environments, the generated axial lines can uniquely represent their individual small-scale spaces. Our algorithms can deal with all the pathological cases identified and discussed previously, thus being more robust than existing ones. However, further research is still needed in the future. How to speed up the automating process remains a critical issue, in particular when generating the axial lines for an urban system involving thousands of buildings or street blocks.

### Acknowledgements

Part of the research was carried out while the authors worked with the Hong Kong Polytechnic University. Thanks to Alasdair Turner for kindly sharing the data sets of Gassin, Barnsbury and National Gallery London, and to the referees for their constructive comments. We also thank Junjun Yin for his assistance in digitizing the maps of the street patterns and Petra Norlund for polishing up our English.

### References

- Batty, M. and Rana, S., 2004. The automatic definition and generation of axial lines and axial maps. *Environment and Planning B: Planning and Design*, 31, 615–640.
- Benedikt, M.L., 1979. To take hold of space: isovists and isovist fields. *Environment and Planning B: Planning and Design*, 6, 47–65.
- Blum, H., 1967. A transformation for extracting new descriptors of form. In: W. Whaten-Dunn, ed. *Models for the perception of speech and visual form*. Cambridge, MA: MIT Press, 362–380.
- Blum, H. and Nagel, R.N., 1978. Shape description using weighted symmetric axis features. *Pattern Recognition*, 10, 167–180.
- Carvalho, R. and Batty, M., 2005. Encoding geometric information in road networks extracted from binary images. *Environment and Planning B: Planning and Design*, 32, 179–190.
- Hillier, B., 1996. *Space is the machine: a configurational theory of architecture*. Cambridge, MA: Cambridge University Press.
- Hillier, B. and Hanson, J., 1984. *The social logic of space*. Cambridge, MA: Cambridge University Press.
- Jacobs, A.B., 1995. *Great streets*. Cambridge, MA: MIT Press.
- Jiang, B., 2009. Ranking spaces for predicting human movement in an urban environment. *International Journal of Geographical Information Science*, 23, 823–837, Preprint, [arxiv.org/abs/physics/0612011](http://arxiv.org/abs/physics/0612011).
- Jiang, B., 2007. A topological pattern of urban street networks: universality and peculiarity. *Physica A: Statistical Mechanics and its Applications*, 384, 647–655.
- Jiang, B., 2009. Street hierarchies: a minority of streets account for a majority of traffic flow. *International Journal of Geographical Information Science*, 23, 1033–1048, Preprint, [arxiv.org/abs/0802.1284](http://arxiv.org/abs/0802.1284).
- Jiang, B. and Claramunt, C., 2002. Integration of space syntax into GIS: new perspectives for urban morphology. *Transactions in GIS*, 6 (3), 295–309.
- Jiang, B. and Claramunt, C., 2004. Topological analysis of urban street networks. *Environment and Planning B: Planning and Design*, 31, 151–162.
- Jiang, B., Zhao, S., and Yin, J., 2008. Self-organized natural streets for predicting traffic flow: a sensitivity study. *Journal of statistical mechanics: Theory and experiment*, P07008, arXiv ePrint: 0804.1630.
- Jiang, B. and Liu, X., 2009. AxialGen: a research prototype for automatically generating the axial map. Presented at the 11th International Conference on Computers in Urban Planning and Urban Management (UPUM), Hong Kong, 16–18 June 2009. Preprint, [arxiv.org/abs/0902.0465](http://arxiv.org/abs/0902.0465).

- Katz, R.A. and Pizer, S.M., 2003. Untangling the Blum medial axis transform. *International Journal of Computer Vision*, 55, 139–153.
- Lynch, K., 1960. *The image of the city*. Cambridge, MA: The MIT Press.
- O'Rourke, J., 1987. *Art gallery theorems and algorithms*. New York: Oxford University Press.
- Peponis, J., *et al.*, 1997. On the description of shape and spatial configuration inside buildings: convex partitions and their local properties. *Environment and Planning B: Planning and Design*, 24, 761–781.
- Peponis, J., *et al.*, 1998. On the generation of linear representations of spatial configuration. *Environment and Planning B: Planning and Design*, 25, 559–576.
- Ratti, C., 2004. Space syntax: some inconsistencies. *Environment and Planning B: Planning and Design*, 31, 487–499.
- Salingaros, N.A., 2005. *Principles of urban structure*. Delft: Techné.
- Simon, H.A., 1962. The architecture of complexity. *Proceedings of the American Philosophical Society*, 106 (6), 467–482.
- Sung, K. and Shirley, P., 1994. Ray tracing with the BSP tree, *In*: D. Kirk, ed. *Graphics gems III*. San Francisco, CA: Morgan Kaufmann.
- Thomson, R.C., 2003. Bending the axial line: smoothly continuous road centre-line segments as a basis for road network analysis. *In*: J. Hanson, ed. *Proceedings of the fourth space syntax international symposium*. University College London, London.
- Turner, A., *et al.*, 2001. From isovists to visibility graphs: a methodology for the analysis of architectural space. *Environment and Planning B: Planning and Design*, 28, 103–121.
- Turner, A., Penn, A., and Hillier, B., 2005. An algorithmic definition of the axial map. *Environment and Planning B: Planning and Design*, 32, 425–444.